



* MODIFIED PER ADA REQUIREMENTS

x*	y*	z*	z ₁ *
CURB HEIGHT	RAMP LENGTH	SIDE SLOPE	SIDE SLOPE
6	5'-6"	4'-7"	5'-6"
7	6'-6"	5'-5"	6'-6"
8	7'-6"	6'-3"	7'-6"



CONSTRUCTION NOTES:

1. SEE CVCS-29 FOR GENERAL NOTES.
2. IF INADEQUATE SPACE EXISTS IN EXISTING SIDEWALK TO PROVIDE 4' MINIMUM BEHIND RAMP, SIDE SLOPE SHALL BE INCREASED TO 12:1 PER TABLE ABOVE.
3. BACK GROOVES MAY BE PLACED WITHIN RAMP SLOPE IF INADEQUATE SPACE IS AVAILABLE IN EXISTING SIDEWALK.
4. THE REMOVAL OF EXISTING CONCRETE CURB, GUTTER, SIDEWALK AND PAVEMENT FOR PEDESTRIAN RAMP INSTALLATION SHALL COMPLY WITH STANDARD DRAWING G-11.



NOT TO SCALE

Revised:	Original approval date: 3-23-94	CITY OF CHULA VISTA	
	Redrawn By: CVM Date: 8-20-01	PUBLIC WORKS DEPARTMENT	
	<i>Clifford Swanson</i>	PEDESTRIAN RAMP DETAIL	CVCS 26
	CITY ENGINEER Date: 11-7-02	TYPES "A-1" AND "B-1" MODIFIED (IN EXISTING SIDEWALK)	